# Infection Control Risk Assessments (ICRA) for Demolition, Renovation, or New Construction Projects

### Site Applicability

All PHC sites.

### **Practice Level**

Advanced Competency for those involved in construction, renovation, or demolition projects:

Project Manager, Patient/Resident Care Manager, Clinical Site Coordinator, Facilities
 Management, Environmental Services Supervisor, Infection Control Practitioner, Industrial
 Hygiene

### **Purpose**

To control airborne and waterborne biological contaminants in occupied patient care areas during periods of demolition and renovation and new construction projects.

### Requirements

- a. The Infection Control Risk Assessment (ICRA) shall be a part of integrated facility planning, design, construction and commissioning activities and will be conducted during the early planning phase of a project, before construction begins, and continue through project construction and commissioning.
- b. The Infection Control Practitioner should be an active member in all phases of the project.
- c. A multidisciplinary team that includes Infection Control, Clinical Staff (having knowledge of the clinical use of the relevant areas), and Facilities Management will conduct a proactive ICRA during the design and planning phase for all demolition, renovation, and new construction projects. The scope of the project may require other subject matter experts to be involved.
- d. ICRAs will focus on prevention, but will also address monitoring, testing, and intervention when problems are identified.

### Responsibilities

- a. Project Manager will:
  - i. Identify at-risk construction, renovation, and demolition activities.
  - ii. Coordinate Class II and higher construction, renovation, and demolition projects with Infection Control, Clinical Staff, Safety, Fire Marshal, Security, Housekeeping, Emergency

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 1 of 19

- Management, Medical Maintenance, Communications, and the contracting officer's representative (COR)/contractor.
- iii. Ensure contract documents require contractors to implement ICRA requirements during construction by including the following, or similar language in all contracts: "INFECTION CONTROL SHALL APPROVE PROJECTS INVOLVING MANIPULATION OF CEILING TILES, PERFORMANCE OF DUST GENERATING ACTIVITIES, MANIPULATION OF HEATING, VENTILATION, AND AIR CONDITIONING (HVAC) SYSTEMS, PLUMBING, AND/OR OTHER MAINTENANCE REPAIRS PRIOR TO THE INITIATION OF THE PROJECT."
- iv. Initiate an ICRA in the design and planning phase for each construction project.
- v. Routinely monitor construction for contractor compliance with the ICRA.
- vi. Inspect construction areas after final cleaning and approve opening/reopening of the area.
- vii. Verify that construction personnel receive orientation and training in the infection prevention and control measures identified on the ICRA prior to start of work.
- b. Infection Control Practitioner will:
  - Identify high-risk patient populations or areas in consultation with hospital staff.
  - ii. Determine whether construction poses sufficient increased risk to require/recommend that patients be moved to an area of the facility that is not affected by construction.
  - iii. Assist the Project Manager in preparing contractor expectations for infection control practices and criteria for emergency work interruptions.
  - iv. Educate staff about risks associated with potential exposure to microbial contamination, inorganic particulates, and volatile organic chemicals resulting from construction activities.
  - v. Inspect construction areas after final cleaning and approve opening/reopening of the
  - vi. Conduct routine surveillance to identify nosocomial illness, initiate environmental and epidemiological investigations (including retrospective reviews) to identify and eliminate sources of infection if more than one case is found, alert clinicians caring for high-risk patients, and establish a system for prospective surveillance for additional cases.
- c. Environmental Services Supervisor will:
  - i. Work with Infection Control to identify areas that need to be damp mopped/cleaned and clean these areas as scheduled.
  - ii. Terminal clean new and renovated areas before admitting or readmitting patients.
  - iii. Coordinate inspection of final cleaning with Infection Control and the Project Manager prior to opening/reopening the area.
- d. Clinical Staff will:
  - i. Work with Infection Control to identify high-risk patients/areas.
  - ii. Follow procedures in approved ICRAs during construction or renovation activities.
- e. Industrial Hygiene will:
  - i. Work with the Project Manager to develop and carry out indoor air quality and ventilation assessments as needed.
  - ii. Work with Infection Control and the Project Manger during environmental investigations.
  - iii. Recommend appropriate personal protective equipment to be worn by construction personnel.

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 2 of 19





- f. Safety Manager will:
  - i. Ensure that the safety committee periodically reviews the effectiveness of the ICRA during construction.
  - ii. Share relevant safety and health information with the risk manager and patient safety manager.

### **Procedure**

Conduct and document ICRAs by completing steps 1 through 6 below.

Effective date: 9/FEB/2023 Page 3 of 19



Step 1. Use the following table to identify the type of construction.

TYPE OF CONSTRUCTION ACTIVITIES (As Marked)						
Construction Type	Description					
	Inspection and Non-Invasive Activities. Includes, but is not limited to:  a. activities that require removal of no more than one ceiling tile or require wall or ceiling panels to be opened  b. painting (but not sanding) and wall covering  c. electrical trim work  d. minor plumbing work that disrupt the water supply to the localized patient care area (i.e. one room) for less than 15 min  e. other maintenance activities that do not generate dust or require cutting of walls or access to ceilings other than for visual inspection					
	<ul> <li>Small scale, short duration activities which create minimal dust. Includes, but is not limited to:</li> <li>a. activities that require access to chase spaces</li> <li>b. where dust migration can be controlled, cutting of walls or ceilings for installing or repairing minor electrical work, ventilation components, telephone wires or computer cables</li> <li>c. sanding or repair of a small area of a wall</li> <li>d. plumbing work that disrupts the water supply of more than one patient care area (i.e. two or more rooms) for less than 30 minutes</li> </ul>					
	Activities that generate a moderate to high level of dust, require demolition, require removal of a fixed building component (e.g. sink) or assembly (e.g. countertop, cupboard) or cannot be completed in a single work shift. Includes, but is not limited to:  a. activities that require sanding of a wall in preparation for painting or wall covering b. removal of floor coverings, ceiling tiles and casework  c. new wall construction  d. minor ductwork  e. electrical work above ceilings  f. major cabling activities  g. plumbing work that disrupts the water supply of more than one patient care area (i.e. two or more rooms) for more than 30 minutes, but less than one hour.					
	Activities that generate high levels of dust and major demolition and construction activities requiring consecutive work shifts to complete. Includes but is not limited to:  a. activities that involve heavy demolition or removal of a complete cabling system b. new construction that requires consecutive work shifts to complete c. plumbing work that disrupts the water supply of more than one patient care area (i.e. two or more rooms) for more than one hour.					

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 4 of 19



Step 2. Use the following table to identify high-risk groups.

INFECTION CONT	ROL RISK GROUPS (as marked)	
Risk Group	Project Areas	
Group 1 Lowest	<ul><li>Office areas</li><li>Unoccupied wards</li><li>Public areas</li></ul>	<ul> <li>Laundry and soiled linen cleaning areas</li> <li>Physical plant workshops and housekeeping areas</li> </ul>
Group 2 Medium	<ul> <li>Patient care areas, unless listed in group 3 or group 4</li> <li>Outpatient clinics (except oncology and surgery)</li> <li>Admission and discharge units</li> </ul>	<ul> <li>Waiting rooms</li> <li>Autopsy and morgue</li> <li>Occupational therapy and Physical therapy areas remote from patient care areas</li> </ul>
Group 3 Medium/High	<ul> <li>Emergency Room (except Trauma)</li> <li>Imaging</li> <li>Labour and Delivery (non-operating)</li> <li>Nurseries for healthy newborns</li> <li>Nuclear medicine</li> <li>Hydrotherapy</li> <li>Echocardiography</li> <li>Laboratories</li> </ul>	<ul> <li>General medical and surgical wards</li> <li>Paediatrics Geriatrics</li> <li>Long-term care</li> <li>Food preparation, serving and dining areas</li> <li>Respiratory therapy</li> <li>Clean linen handling and storage areas</li> </ul>
Group 4 Highest	<ul> <li>Intensive care units</li> <li>Operating rooms (including pre, induction PACU and scrub areas)</li> <li>Anaesthesia storage areas and workrooms</li> <li>Oncology units and outpatient clinics</li> <li>Transplant units and outpatient clinics</li> <li>Wards and outpatient clinics for patients with AIDS or other immunodeficiency diseases</li> <li>Dialysis units</li> <li>Critical care nurseries</li> <li>Labour and delivery operating rooms</li> <li>Cardiac catheterization and angiography</li> <li>Cardiovascular and cardiology patient areas</li> </ul>	<ul> <li>Trauma rooms</li> <li>Protective environment isolation rooms</li> <li>Tissue culture laboratories</li> <li>Bronchoscopy</li> <li>Cystoscopy</li> <li>Pacemaker insertion rooms</li> </ul>

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 5 of 19

### Step 3. Use the following table to define risk. See <u>Appendix A</u> for description of IPAC practices by class and <u>Appendix B</u> for Class III and IV projects.

CONSTRUCTION ACTIVITY / INFECTION CONTROL MATRIX  Infection Control Permit will be required when the Construction Activity and Risk Level indicate that Class III and Class IV control procedures are necessary.									
	CONSTRUCTION ACTIVITY								
RISK LEVEL	TYPE "A"	TYPE "B"	TYPE "C"	TYPE "D"					
GROUP 1	CLASS I	CLASS II	CLASS II	CLASS III/IV					
GROUP 2	CLASS I	CLASS II	CLASS III	CLASS IV					
GROUP 3	CLASS I	CLASS III	CLASS III/IV	CLASS IV					
GROUP 4	CLASS I/II/III	CLASS III/IV	CLASS III/IV	CLASS IV					

Effective date: 9/FEB/2023 Page 6 of 19

# Step 4. Use the following questions to further assess scope and risk. Assign to each part who is responsible and how it is monitored.

INF	INFECTION CONTROL RISK ASSESSMENT:									
1.	Identify the areas surrounding the project area, assessing potential impact:									
Unit	Below	Unit Above	Lateral	Lateral	Behind	Front				
Risk	Group:	Risk Group:	Risk Group:	Risk Group:	Risk Group:	Risk Group:				
2.	. Identify the specific site wherein the activity will occur (e.g. patient room, medication room, etc.):									
3.	probable ou Maintenand	ential risks relate utages and coordi ce and IPAC. Wor lant Maintenance	nate arrangemer k hours must be	its with clinical de	partment manag	er, Plant				
4.	Identify cor walls, 6 mL	ntainment measu Poly, etc.):	res, using prior as	sessment. Identi	fy types of barrie	rs (e.g. solid				
5.		otential risk of wa e.g., wall, ceiling,		ere a risk due to	compromising str	uctural				
6.	Work hours	: Can or will the v	vork be done dur	ing non-patient c	are hours?					
7.	Do plans all	ow for adequate	number of isolati	on/negative airflo	ow rooms?					
8.	Do the plan	s allow for the re	quired number &	placement of hai	nd hygiene statio	ns?				
9.	Do the plan	s for clean and sc	oiled utility access	and use make se	nse?					
10.	How will ho	usekeeping work	around the proje	ect?						
11.	Where will	materials be hand	dled and stored?							
12.	How will de	bris be removed	(containment me	thod and times?)	:					
13.	Plans for the following (who is responsible? how's it implemented, documented and monitored?):									
	<ul> <li>a. Traffic flow:</li> <li>b. Housekeeping:</li> <li>c. Debris removal (containment method and times?):</li> <li>d. Hours/days worked:</li> <li>e. Materials handling &amp; storage:</li> </ul>									

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 7 of 19



### **Step 5. Complete the Infection Control Construction Permit.**

INFECTION CONTROL CONSTRUCTION PERMIT											
Project Descri	ption/Numbe	er:			Project Type:						
					MaintenanceRenovation						
			De	emolition	_	C	onstr	uction			
					0	ther:					
Estimated Sta	rt Date:				Estima	ted Comp	oletio	n Date	:		
Facility Project	t Manager:				Phone	Number:					
Project Contra	actor:				Phone	Number:					
Infection Con	trol Officer:				Phone	Number:					
Location:					Area Supervisor/Phone Number:						
Construction	Туре:		Risk Grou	-	Risk Assessment:						
(Circle One)			(Circle O	ne)			(Circ	le One	2)		
A	B C D		Low Medium-Hig		Medium igh High			I II	III	III/IV	IV
Projected Util	ity Outages Ir	npact	ing Infecti	on Con	trol (Ma	rk all tha	t app	ly)			
Electrical	Potable Water	HV	AC Med Vacu					Other:			
List All Constr Medical Equip			-			, Vibratio	n, and	i/or Ir	nterfe	erence v	with

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 8 of 19

INFECTION CONTROL CONSTRUCTION PERMIT

# Infection Control Measures: (Contractor/PM to initial and date any Class III, IV, and Additional Requirements). See <a href="Appendix A">Appendix A</a> for more information.

Requirements). See Appendix A for more information.							
Risk Class	Measures						
Class I	<ol> <li>Review Infection Control Construction Agreement before work begins.</li> <li>Execute work by methods to minimize raising dust from construction operations.</li> <li>Protect patient care equipment and supplies from dust exposure.</li> <li>Immediately replace any ceiling tile displaced for visual inspection.</li> <li>Report discoloured water and water leaks to maintenance.</li> </ol>						
Class II	<ol> <li>Class I measures will be followed, plus:</li> <li>Determine a safe route for the transportation of clean or sterile supplies and equipment away from the construction area</li> <li>Establish traffic patterns for construction workers that avoid patient care areas.</li> <li>Provide active means to prevent air-borne dust from dispensing into atmosphere.</li> <li>Water mist work surfaces to control dust while cutting.</li> <li>Seal unused doors with duct tape.</li> <li>Block off and seal air vents.</li> <li>Wipe work surfaces with disinfectant.</li> <li>Contain construction waste before transport in tightly covered containers.</li> <li>Wet mop and/or vacuum with HEPA filtered vacuum before leaving work area.</li> <li>Place dust mat at entrance and exit of work area.</li> <li>Remove or isolate HVAC system in areas where work is being performed.</li> <li>Flush potable water lines in the construction area and adjacent areas before reuse.</li> </ol>						
Class III	<ol> <li>Class I and II measures will be followed, plus:</li> <li>Obtain Infection Control permit before construction begins.</li> <li>Isolate HVAC system in area where work is being done to prevent contamination of duct system.</li> <li>Complete all critical barriers or implement control cube method from floor to true ceiling (includes the areas above false ceilings) before construction begins.</li> <li>Maintain negative air pressure within work site utilizing HEPA equipped air filtration units.</li> <li>Do not remove barriers from work area until complete project is thoroughly cleaned by Housekeeping.</li> <li>Vacuum work with HEPA vacuums.</li> </ol>						

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 9 of 19

INFECTION CONTROL CONSTRUCTION PERMIT							
	<ol> <li>Wet mop with disinfectant.</li> <li>Remove barrier materials carefully to minimize spreading of dirt and debris associated with construction.</li> <li>Contain construction waste before transport in tightly covered containers.</li> <li>Cover transport receptacles or carts. Tape covering.</li> <li>Remove or isolate HVAC system in areas where work is being performed.</li> <li>Consider hyper-chlorinating or superheating stagnant potable water – Review LMFM Potable water systems sanitation documentation requirements for guidance.</li> </ol>						
Class IV	<ol> <li>Class I, II and III measures will be followed, plus:</li> <li>Construct anteroom at access points to the construction area if access is from within the health care facility</li> <li>Place walk off mat outside the anteroom in patent care areas and inside the anteroom</li> <li>Ensure construction workers:</li> <li>Leave the construction area through the anterooms so they can be vacuumed using a HEPA vacuum cleaner before leaving work site or,</li> <li>Wear protective clothing that is to be removed each time they leave the construction area and before going into patient care areas.</li> <li>Repair holes in walls within 8 hours or seal them temporarily</li> <li>Ensure that ventilation systems are working properly in adjacent areas</li> </ol>						

### **Other Risk-Reduction Strategies:**

- Keep patient doors adjacent to the construction area closed.
- Seal exterior windows to minimize infiltration from excavation debris.
- Designate alternate routes in the facility that detour staff, patients, and visitors around the construction site.
- Schedule major construction projects during winter months when risk of fungal infection is lowest.
- Designate a construction-only elevator, entrance, and walkway for construction crew.
- Remove construction debris through a window on floors above the ground level.
- Relocate high-risk patients to an area removed from the construction site.
- Post signage related to non-authorized entry into the work area.
- Designate storage areas for construction materials.
- Train and educate healthcare staff, facility workers, and construction workers: Infection Control Exposure Control Plans, Hazardous Chemicals, Life Safety, Accident Reporting, First Aid, Personal Protective Equipment, Reporting unexpected environmental emergencies (e.g., lead paint, asbestos, etc.)
- Other:

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 10 of 19



# Step 6. Complete daily monitoring to ensure workers/contractors follow infection control guidelines and policies.

CONSTRUCTION SITE SURVEY TOOL		
Date:	Time:	_
Barriers		
Construction signs posted for the area	□ Yes	No
Doors properly closed and sealed	□ Yes	No
Floor area clean, no dust tracked	□ Yes	No
Air handling		
All windows closed behind barrier	Yes	No
Negative air at barrier entrance	□ Yes	No
Negative air machine running	□ Yes	No
Project area		
Debris removed in covered container daily	□ Yes	No
Designated route used for debris removal	□ Yes	No
Trash in appropriate container	□ Yes	No
Routine cleaning done on job site	□ Yes	No
Traffic control		
Restricted to construction workers and necessary staff only	□ Yes	No
All doors and exits free of debris	□ Yes	No
Dress code		
Appropriate for the area (OR, CSS, OB, BMTU)	□ Yes	No
Required to enter	□ Yes	No
Required to leave	Yes	No

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 11 of 19



Area Surveyed\_

Date:

# Step 7. Complete final infection control inspection upon completion of construction/renovation.

Date\_

	k yes, no, or N/A for each cr	riteria. A	satisfa	ctory re	view is required prior to reopening
any unit/department.	riteria	Yes	No	N/A	Comments
I. Contractor Final C		163	140	IN/A	Comments
	ntal surfaces free of				
	al construction dust				
b. Installe	ed equipment and				
cabine	ts properly cleaned				
01 00111101	rs cleaned and removed				
II. HVAC System					
	cleaned if not isolated				
	lace and operational				
	balanced as specified	-			
III. Plumbing System		-			
a. No visible leak	-				
b. Plumbing syste hours prior to d	em flushed within 24				
c. Sinks functions		+		_	
IV. Equipment	u				
a. Soap/towel dis	nensers/hand				
sanitizers insta					
b. Refrigerators -	checklist for				
temperature co	ntrol				
	eaned and flushed				
V. Final Cleaning					
<ul> <li>a. Housekeeping</li> </ul>	final cleaning				
completed		_			
VI. Environmental R					
a. Completion of	Environmental Rounds				
their qualified repr plan for the specific CSA Z317.13-17. The	esentative shall develor c construction project, vone ne plan shall describe th	p and so which so ne proce	ubmit hall be edures	for ap consi proc	ruction projects the constructor or proval a written infection control stent with the requirements of the esses, and safeguards that will be we measures throughout the project.
Date:	Project Manager's Sign	ature:			
Date:	Infection Control Signa	ture:			
Date:	Multi Disciplinary Tean	n's Sign	atures	:	

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Constructor Signature:

Effective date: 9/FEB/2023 Page 12 of 19

### References

- Association for Professionals in Infection Control and Epidemiology. (2015). Infection Prevention Manual for Construction & Renovation. Arlington, VA: Association for Professionals in Infection Control and Epidemiology. (See also: Infection Prevention Manual for Construction & Renovation, 2019 Addendum, available at <a href="https://www.apic.org/store">www.apic.org/store</a>)
- American Society of Heating, Refrigerating and Air-Conditioning Engineers. (2017). Normative Note t for Table 7.1. In: ASHRAE Standard 170-2017 Ventilation of Health Care Facilities (ANSI/ASHRAE/ASHE Approved). Atlanta, GA: American Society of Heating, Refrigerating and Air-Conditioning Engineers.
- Canadian Construction Association. (2018). 82-2004 Mould Guidelines for the Canadian Construction Industry. Available from <a href="https://www.cca-acc.com/wp-content/uploads/2019/02/Mould-guidelines2018.pdf">https://www.cca-acc.com/wp-content/uploads/2019/02/Mould-guidelines2018.pdf</a>
- Canadian Standards Association (CSA) Group (2017). https://www.csagroup.org/standards/
- Couch, L.H., Herwaldt, L.A., & Dickey, L.L. (2018) Infection Prevention in Design, Renovation, and Construction in Lautenbach, E. Malani, P.N., Woeltje, K.F., Han, J.H., Shuman, E.K. Marschall, J., Practical Healthcare Epidemiology; Cambridge University Press

Environmental Abatement Council of Ontario. (2013). DOP/PAO Testing Guidelines

Institute of Environmental Science and Technology. (2022). RP-CC001.4 92005 Hepa and Ulpa Filters.

Health Canada. (2001). Construction-related Nosocomial Infections in Patients in Health Care Facilities:

Decreasing the Risk of Aspergillus, Legionella and Other Infections. *Canada communicable disease report, 27 Suppl 2,* i–46. Available from

https://publications.gc.ca/collections/Collection/H12-21-3-27-2E.pdf

Effective date: 9/FEB/2023 Page 13 of 19

carts.

### Appendix A: Description of Required Infection Control Precautions by Class

### Description of Required Infection Control Precautions by Class

#### **During construction project** Upon completion of project 1. Use methods that minimize dust. Clean work area when task is completed. 2. Immediately replace a ceiling tile displaced for visual inspection. 1. Prevent dust from dispersing into air. 1. Wipe work surfaces with disinfectant. 2. Use mist (water) on work surfaces to control dust 2. Wet mop and/or vacuum area with HEPA filtered while cutting. vacuum before leaving. 3. Seal unused doors with duct tape. 3. Re-integrate HVAC system. 4. Block off and seal air vents. 5. Place dust mat at entrance and exit of work area 6. Remove or isolate HVAC system in work areas. 7. Contain construction waste in tightly covered containers before transport. 1. Isolate HVAC system in area where work is being Do not remove barriers from work area until done to prevent contamination. completed project is inspected by the owner's Safety Department and Infection Control Department and 2. Complete all critical barriers, ie., sheetrock, plywood, thoroughly cleaned by the owner's Environmental plastic, to seal work area from non-work area or use Services Department. control cube method before construction begins. Remove barrier materials carefully to minimize 3. Maintain negative air pressure within work site; use spreading dirt and debris created by construction. HEPA equipped air filtration units. Vacuum work area with HEPA filtered vacuums. 4. Contain construction waste in tightly covered containers before transport. Cover transport Wet mop area with disinfectant. Do not sweep. receptacles or carts. Re-integrate HVAC system. 1. Isolate HVAC system in area where work is being Do not remove barriers from work area until done to prevent contamination of duct system. completed project is inspected by the owner's Safety Department and Infection Control Department and 2. Complete all critical barriers, ie., sheetrock, plywood, thoroughly cleaned by the owner's Environmental plastic, to seal area from non-work area or implement Services Department. control cube method before construction begins. Remove barrier material carefully to minimize Maintain negative air pressure within work site; use spreading dirt and debris created by construction. HEPA-equipped air filtration units. 4. Seal holes, pipes, conduits, and punctures. Vacuum work area with HEPA-filtered vacuums. 5. Construct anteroom. All personnel must use Wet mop area with disinfectant. Do not sweep. anteroom so they can be vacuumed using a HEPA vacuum cleaner before leaving work site or they can Re-integrate HVAC system. wear cloth or paper coveralls that are removed each time they leave the work site. 6. All personnel entering work site are required to wear shoe covers and change them each time they exit the 7. Contain construction waste before transport in tightly covered containers. Cover transport receptacles or

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 14 of 19



### Appendix B: Class III and IV Construction, Renovation, and Maintenance Projects

Class III & IV Construction, Renovation & Maintenance Projects

Based on the CSA Z317.13-12 Standard

**Project:** 

**Start Date:** 

		Cor	Compliance		
	Element	Yes	No	NA	Notes
1.0	Before Project Begins				
1.1	MDT meetings set-up and identification of essential services that could be disrupted				
1.2	Discussion with staff in the work area for awareness and education of infection risks and work activities				
1.3	ICRA form completed and signed by PM and ICP				
1.4	Any changes to project scope are reviewed with ICP				
1.5	Exposure of patients to work area has been minimized				
1.6	High risk patients have been moved away from work area if safe levels of indoor air quality cannot be ensured				
1.7	Work area is restricted to authorized personnel.  If this is not possible, ensure transportation routes havebeen developed for:  Patients Staff & visitors Clean/sterile supplies				
1.8	Traffic patterns for construction workers and removal of equipment/materials that avoid patient care areas havebeen developed				
1.9	If needed, dedicate elevators for construction- related activities				
1.10	Patient care equipment and supplies are removed and/or protected from work area				

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 15 of 19



		Cor	Compliance		
	Element	Yes	No	NA	Notes
1.11	<ul> <li>Water disruptions:</li> <li>Temperature standards established (CSA Z317.1)</li> <li>Alternate potable water source, if needed</li> <li>Appropriate method for cleaning water systemsaffected by major plumbing activities (flushing, superheating, hyperchlorination, etc.)</li> <li>Scheduled during low activity (evenings/weekends)</li> </ul>				
2.0	During Project				
2.1	Dust suppression within work area (water misting work surfaces, HEPA-filtered vacuums, walk-off sticky mats, etc.)				
2.2	Impermeable dust barrier erected from floor to the true ceiling, consisting of two layers of 6 mil poly and gypsum wallboard protective layer				
2.3	Anteroom (when used) is constructed at access pointsinto work area (if access is from within the hospital)				
2.4	Negative pressure within work zone maintained with airhandling units (AHUs) with HEPA filters  • Exhausted directly outside, away from intake vents, or recirculated to a Risk Group I or II area (as approved by the MDT)  • Maintain pressure differential of 7.5 Pa betweenwork area and hospital zone (equivalent to 0.03 inches of water)  AHUS leak-tested and performance verified at				
2.5	AHUs leak-tested and performance verified at beginning of project (or verified this was done in past 12 months)				

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.

Effective date: 9/FEB/2023 Page 16 of 19



		Compliance		nce	
	Element	Yes	No	NA	Notes
2.6	Proper signage forbidding access into work area (unlessauthorized personnel) and with key project staff names and 24-hour contact numbers posted				
2.7	Discoloured water, water leaks, water interruptions and dust migration are reported immediately to PM and IPAC				
2.8	All potential air leaks from the work area are sealed with plastic/tape (doors, plumbing penetrations, intake/exhaust vents, electrical outlets, etc.)				
2.9	Dust barrier integrity is inspected frequently and breaches are immediately repaired				
2.10	Ongoing monitoring and documentation of negative pressure & HEPA filters replacements				
2.11	Walk-off mats replaced daily and/or when visibly soiled				
2.12	Construction workers to wear protective clothing that is removed or HEPA vacuum clothing before leaving the work area; all workers to follow proper hand hygiene practices				
2.13	Work area is wet mopped and/or HEPA vacuumed asnecessary throughout project				
2.14	Supplies and equipment are wiped clean and/or covered during transport through the hospital				
2.15	Debris is covered and wiped/vacuumed clean before being removed from the work area and transported through thehospital				
2.16	Regular ICP visits to the work site which are documented				
3.0	End of Project				

This material has been prepared solely for use at Providence Health Care (PHC). PHC accepts no responsibility for use of this material by any person or organization not associated with PHC. A printed copy of this document may not reflect the current electronic version.



		Compliance		nce	
Element		Yes	No	NA	Notes
3.1	If water lines shut down or accessed during construction, they are flushed before reusing (minimum of 10 minutes)				
3.2	Work area is thoroughly cleaned and barriers are cleaned before dismantling				
3.3	Air filters changed/cleaned as necessary in work areas; andventilation systems are functioning properly and are cleaned if contaminated during work activities				
3.4	Dust barriers/anterooms removed carefully to minimize dust migration				
3.5	Final visual inspection of the of the work area and terminal clean before patients are readmitted to the area				
3.6	Review project and effectiveness of preventative measures				

Effective date: 9/FEB/2023 Page 18 of 19



### DOCUMENT #B-00-16-13001

First Released Date:	30-JAN-2015
Posted Date:	09-FEB-2023
Last Revised:	09-FEB-2023
Last Reviewed:	21-NOV-2022
Approved By:	PHC
(committee or position)	IPAC Standards Committee
Owners:	PHC
(optional)	IPAC

Effective date: 9/FEB/2023 Page 19 of 19